



Network Engineering Technologies  
3140 Deming Way  
Middleton, WI 53562  
www.nettechnology.com

Vendor: 60426  
Purchase Order: 651326-1314720-S80188364  
Work Order: 1314720  
Service ETA: 9/23/2021 9:00 AM  
\*Purchase Order MUST appear on all invoices and  
emailed to apinbox@nettechnology.com or invoice will be  
rejected, Invoice must match this Purchase Order Receipt.

#### Site Location Information

**Customer:** ShopperTrak  
**Site Number:** S80188364  
**Location:** Lululemon - 10831  
2860 Cumberland Parkway Southeast Suite  
1358  
Atlanta, GA 30339  
( ) -  
**Site Contact:** Lululemon

#### Technician Information

**Technician Name:** Thishawn Bessor  
**Technician Phone:** (347) 777-2900  
**Techs Manager:**  
**Manager Phone:** 4058021262

**\*\*\* MUST CALL UPON ARRIVAL AND BEFORE SITE DEPARTURE \*\*\***

#### NET Contact Info:

Please Call: 608 827-2271 \*Your call will be handled in the order received\* The  
following Login information is needed: your name, Company Name, work order#,  
callback number(mobile#)

#### Scheduling

1 billable technician required Arrival Time: 9/23/2021 9:00 AM

#### Scope of Work

Tyco ShopperTrak - BrickStream Install - lululemon - Cumberland Mall Seasonal Store

Must arrive onsite at time designated on work order - DO NOT AUTO LOG IN

Safety Protocol Requirements:

1. Techs to wear face coverings and gloves at all times when entering, working in, or exiting stores.  
a. This can include any of the following based on CDC guidelines: reusable or disposable masks.
2. Techs to maintain social distancing while in stores and follow all posted instructions for customer queuing/metering.
3. Techs to refrain from visiting stores if they have a fever of 100.4 F (37.94 C) or higher, or have exhibited any symptoms of COVID-19 within 14 days of the scheduled visit, (ex: fever, cough, shortness of breath or difficulty breathing, chills, repeated shaking with chills, muscle pain, headache, sore throat, new loss of taste or smell).  
a. Or if in the last 14 days, they have been out of the country, traveled by plane/cruise ship or been to areas known to have high concentrations of COVID-19 infections, or been in close contact with a person(s) with a positive or presumed positive COVID-19 case.
4. If a technician is diagnosed with COVID-19 or shown symptoms of COVID-19 within 2 weeks of visiting a store, inform NET/ShopperTrak of the diagnosis.

ATTENTION: A Windows based Laptop and Smartphone required. Do not leave in vehicle. No exceptions.

#### ***New installation.***

*Orbit Type & Connectivity: Brickstream- IP*

*Store Open: N*

*Date Requested: 9/23*

Notes: Brickstream install. EQ to be shipped directly to tech shop. Addresses to be sent to Tamiya. Tech to plug into port # 5 or 6



Network Engineering Technologies  
3140 Deming Way  
Middleton, WI 53562  
www.nettechnology.com

Vendor: 60426  
Purchase Order: 651326-1314720-S80188364  
Work Order: 1314720  
Service ETA: 9/23/2021 9:00 AM  
\*Purchase Order MUST appear on all invoices and  
emailed to apinbox@nettechnology.com or invoice will be  
rejected, Invoice must match this Purchase Order Receipt.

Pre-Cabled: Yes

# of Orbits: 1

- Ceiling Height: XXX Tech must be able to reach 12ft ceiling.
- Precabled: NO/YES \*\*\*Tech must be prepared to run cable BUT must notify NET before doing so.
- Number of Entrances:
- Number of Devices:
- Switch Port:

\*\*\*Special instructions:

\*\*\*Additional Scope:

ATTENTION: A Windows based Laptop and Smartphone required. Do not leave in vehicle. No exceptions.

-----  
\*\*\*Required Materials:\*\*\*\*\*

\*\*Tech should bring patching compound to fill any holes left when mounting orbit/s.\*\*

Cat5e or cat6 cable

Minimum 10ft ladder

Misc Cat5 materials: jacks, surface mount boxes, patch cords, etcetera...

\*\*\*\*\*Required Tools:\*\*\*\*\*

Digital camera or smartphone

Cat5e/Cat6 tester

Butt set

Toner

Punch tool

Standard cabling tools

Standard hand tools and power tools  
-----

1. LOG IN with NET Support 608-827-2271 opt 4. - Please have Site ID(Commonly S80XXXXX) or Work Order ready (10XXXXX)
2. Find manager or GC and locate equipment shipped to site. (take photos of Equipment and serial numbers)
3. INSTALL Brickstream devices in accordance with the installation manual. Inform NET of any delays.
4. If Scope states "Pre-Cabled: Yes" and site is NOT then tech MUST get approval from NET before running cable.
5. LABEL both ends of each cable and the POE injector if applicable.
6. Take clear PHOTOS. Photos will be reviewed while the technician is onsite. Blurry or small photos will not be accepted. If there is an issue sending photos tech should notify NET immediately.
  - Equipment serial Numbers
  - Close up of mounted device
  - Wide shot showing doorway floor to ceiling, install location
  - Wide shot of network equipment/data rack
  - Close up of port used for device cable, showing label
  - Wide shot showing POE injector location
6. E-MAIL photos to dss@nettechnology.com, put work order in brackets for the Subject.  
- Example [1065432]
7. TESTING: Call NET for configuration, testing at 608-827-2271 opt 4.  
NET Support will ask additional questions to create an FDS. Note the following information:
  - The entrance height, width, mounting height: H\_\_\_\_\_ W\_\_\_\_\_ MH\_\_\_\_\_
  - Ceiling, floor, lighting type at entrance, and door type: \_\_\_\_\_
  - Note any device IP settings, serial numbers, and MAC addresses

Call NET for configuration, testing and log out 608-827-2271 opt 4.

\*YOU MUST LOGIN AND OUT WITH NET\*

\*FAILURE TO COMPLY WITH ANY PORTION OF THIS WORK ORDER WILL RESULT IN NON-PAYMENT\*

