



By accepting this work order and performing the mentioned above services you are accepting the terms and conditions set forth in the Master Contractors Agreement.

CUSTOMER INFORMATION:

Customer: Wal*Mart Stores Inc.
Site: Supercenter #1363
Address: 1681 EATONTON RD
MADISON, GA 30650
Corner Address:
Phone: 706-342-9988

Requested By: 20728
Problem Code: 100 Misc Multi-Site Project

CROSSCOM NATIONAL INFORMATION:

Contact: Joseph Helms

Log in and out via IVR: (800) 820-9229
Fax D&A to: (800) 933-5538
Questions? Call: (800) 820-9229

BRIEF STATEMENT OF WORK & COMMENTS

Walmart - 2021 Project Swipe Up - Quote 43190
Install 14 screens and 14 players in the different areas.
3 - Electronics
3 - Deli
3 - Bakery
2 - Auto Center
2 - Money Center (mounted horizontally)
1 - Pharmacy (mounted vertically)

TRIP INFORMATION

Arrival Date	Arrival Time	Time Zone	Trip Description	# Of Techs
08/19/2021	09:00 PM	EDT	Media Player and Screen Install	2

TECHNICAL NOTES:

Technicians will install, test and verify proper operation of Brightsign media players and screens (55" displays) at designated locations within the store. The number of players & screens will vary by site and will be noted on the work order.

Technicians will need to identify switch ports being used and work with CrossCom Help Desk to verify port configuration.
Screens will be installed in various configurations based on location (pole mount and wall mount)
Typical locations for screens include: Bakery, Deli, Electronics, Money Center, Auto Care, etc
Data, Electrical and the Pole mount hardware have been installed by Others.

- * Trips All work will be completed in (1) Trip by (2) Technicians AFTER normal business hours.
- * Tools Needed: Laptop with Aircard, Digital Camera, Label Maker, Cat 5r tester, Toner/Tracer, Ladders (8, 10, 12')
- * Materials: Technician will supply hardware for mounting the TVs.
- * The technicians will need to log in and out with the CrossCom Project Team @ 800-820-9229.
- * Deliverables will be required to validate work completion and craftsmanship. All deliverables must be uploaded through the vendor portal prior to leaving the work site. Failure to provide deliverables will result in non-payment.

MATERIAL ON ORDER

Part Number	Part Description	Provided By	Quantity
FSRMISC	Toggler Snap Toggle Bolts (1/4" X 2-1/2") Wall Mount (4 per	VFT	1.00
FSRMISC	M8-1.25 X 40 Screws (4 per pole mount TV)	VFT	11.00

SPECIAL TOOLS

Description	Provided By
Lift Rental, 19' Electric Scissor Lift, Daily	CrossCom
Laptop with Aircard	VFT
Digital Camera	VFT
Label Maker	VFT
Cat 5r tester	VFT



Toner/Tracer
Ladders (8, 10, 12')
Lift Rental, 19' Electric Scissor Lift, Weekly

VFT
VFT
CrossCom

OPTIONAL ITEMS (Confirm with CrossCom before performing any of these activities.)

Description
None

DELIVERABLES

Required before last trip checkout.

Description	Acceptance Criteria	Type
Delivery & Acceptance		Delivery & Acceptance
Pharmacy Screen	Overall view with content playing	Pictures
Electronics Screen - Photo Lab	Overall view with content playing	Pictures
Electronics Screen - Entertainment	Overall view with content playing	Pictures
Electronics Screen - Wireless	Overall view with content playing	Pictures
Money Center Screen - Menu Board	Overall view with content playing	Pictures
Money Center Screen - Services	Overall view with content playing	Pictures
Auto Center Screen - Menu Board 1	Overall view with content playing	Pictures
Auto Center Screen - Menu Board 2	Overall view with content playing	Pictures
Bakery Screen - Cakes	Overall view with content playing	Pictures
Bakery Screen - Cakes and Cupcakes	Overall view with content playing	Pictures
Bakery Screen - Custom Cakes	Overall view with content playing	Pictures
Deli Screen - Lunch	Overall view with content playing	Pictures
Deli Screen - Party Tray	Overall view with content playing	Pictures
Deli Screen - Chicken	Overall view with content playing	Pictures



DELIVERY & ACCEPTANCE (D & A):

Trip # _____ Date _____ On-Site At _____ Off-Site At _____

Manager Signature _____ Manager Printed Name _____

Additional Trip Required? Yes / No

Description of Work: _____

Customer Abuse: Yes / No Explain: _____

Trip # _____ Date _____ On-Site At _____ Off-Site At _____

Manager Signature _____ Manager Printed Name _____

Additional Trip Required? Yes / No

Description of Work: _____

Customer Abuse: Yes / No Explain: _____

CHECKLIST

1. What delays (if any) did you have on site? _____
2. What is the printed name of the Walmart employee that confirmed everything is working? _____
3. How many TVs did you mount in the Money Center (should be 2)? _____
4. How many TVs did you mount in Electronics (Typically 3)? _____
5. How many TVs did you mount in the Auto Center (Typically 2)? _____
6. How many TVs did you mount in the Deli (Typically 3)? _____
7. How many TVs did you mount in the Bakery (Typically 3)? _____
8. How many TVs did you mount in the Vision Center (Typically 2 - Portrait mounted)? _____
9. How many TVs did you mount in the Pharmacy (Typically 1 - Portrait mounted)? _____
10. What are the switch, ports and MAC addresses assigned for Money Center? (Ex: GM3 - 1/0/10 MAC: 12345CF990) _____
11. What are the switch, ports and MAC addresses assigned for Auto Center? (Ex: TLE1 - 1/0/10 MAC: 12345CF990) _____
12. What are the switch, ports and MAC addresses assigned for Deli? (Ex: GRC1 - 1/0/10 MAC: 12345CF990) _____
13. What are the switch, ports and MAC addresses assigned for Bakery? (Ex: GRC1 - 1/0/10 MAC: 12345CF990) _____
14. What is the switch, port and MAC address assigned for Pharmacy? (Ex: RX1 - 1/0/10 MAC: 12345CF990) _____

This document must be signed by the site manager and by the technician. See the final page.



-
15. What are the switch, ports and MAC addresses assigned for the Vision Center? (Ex: GM2 - 1/0/10
MAC: 12345CF990)
16. What are the switch, ports and MAC addresses assigned for Electronics? (Ex: PIC1 - 1/0/10 MAC:
12345CF990)



COMMENTS & SIGNATURES

Comments _____

Manager Signature _____ Date & Time _____

Technician Signature _____ Date & Time _____